Bharat Bijlee

Data sheet for motors

Manufacturer	Bharat Bijlee Ltd.		Customer	
Type of motor	3 Phase Induction Motor		BBL Enquiry reference No	
Quantity			Customer P.O.Number	
Application	**CUSTOMER TO FURNISH**		W.O. No. / SAP No.	
Tag no.			Output kW / pole	30 / 8P
BBL type tef.	2J25M813		Frame size	MJ250

Installation details			*Applicable standards (latest edition)*	
Area classification (Safe / Hazardous)	Hazardous		Performance: IS/IEC 60034-1 Maintenance IS:900	FLP Motors: IS/IEC 60079-1
Location: indoor/outdoor/deck	Indoor		Dimensions: IS 1231/IS 2223/IS:8223	
Altitude (meters)	1000 or less		Vibrations: IS 12075	
			Noise level: IS 12065	

Hazardous area details			*Supply conditions and permissible variations (grid supply)*		
Area classification GAS (Zone 1/Zone 2)	ZONE I		Number of phases	Three	
Gas group	IIA, IIB		Voltage (Volts) and permissible variation	415	±10%
Temp.class	T4		Frequency (Hz) and permissible variation	50	±5%
Type of Explosion protection (FLP/Type 'e'/Type 'n')	Ex d		Combined variation (absolute sum)	±10%	
Approving authority for hazardous area	If Coal Mine application then DGMS else PESO				

Electrical parameters

Starting performance

Method of starting	DOL		Starting current (%FLC)	550	
Load speed (rpm)	CUSTOMER TO FURNISH		Starting torque (%FLT)	200	
Motor GD^2 (kgm^2)	3.25		Pull out torque (%FLT)	220	
Load GD^2(kgm^2)	CUSTOMER TO FURNISH		Locked rotor withstand time (hot/cold) (sec)	15 / 30	
Load torque-speed curve	Parabolic TS curve		Number of consecutive starts (hot/cold) (nos.) provided Load GD2 = Motor GD2	2 / 3	
Starting time at rated voltage (sec)	PLEASE FURNISH ALL ABOVE DETAILS				

Running Performance

Efficiency class	IE2			Duty and designation	Continuous (S1)		
Ambient temp./temp.rise by resistance (deg.C)	45	/	75	CDF/Equivalent starts per hour/FI	-		
Enclosure	TEFC (TOTALLY ENCLOSED FAN COOLED)			Insulation class / utilisation class on DOL	F/B		
Full load current (FLC) amps.	56.7			Rotor type (Squirrel Cage/ Slip ring)	Squirrel Cage		
Full load speed (rpm)	730			Rotor voltage/rotor current (RV/RA) (Volts/Amps)	Not applicable		
Full load torque (FLT) kg-m	40			Stator/rotor time constant (min)	108/146		
Efficiency in % at FL/0.75FL/0.5FL	89.8	89.8	89.0	Power factor at FL/0.75FL/0.5FL	0.82	0.80	0.72

Mechanical parameters

Mounting	B8		Mounting dimensions	Refer GA drawing
Shaft extention	Single cylindrical		Direction of rotation viewed from DE	Clockwise
Degree of protection	IP 55		Suitable for bidirectional rotation	Yes
Method of cooling (TEFC/forced cooled/TESC)	TEFC (IC 411)		Paint type	Acid Alkali Proof
Net weight of motor (kgs.)	570		Paint shade	632 as per IS 5
			Earthing provision (two terminals on stator body)	Yes

Bearings			*Terminal box*	
Coupling (Direct/flexible/Belt & Pulley/Gearbox)	Direct		Terminal box location when viewed from DE	As per GA drawing
Dimenssions of pulley (OD x width) mm	-		Direction of cable entry	As per GA drawing
Bearings (roller/ball/angular contact)	Ball /Ball		Cable size and type(Aluminium)	2R X 3C X 120 SQ MM
Bearing size DE/NDE	6215 C3 / 6215 C3		Earthing provision (one terminal in TB)	Yes
Type of lubrication	SKF LGMT3- GREASE		No of phases/Winding connection/number of terminals	3 / DELTA / 6

Accessories

RTDs - 3 numbers simplex (w/o controller)			Arrow plate for direction of rotation	
BTDs - 1 number per bearing (w/o controller)			Double compression glands (main cable)	
Space heaters - single phase 50z, 230V			Double compression glands (Space heater/thermisters/RTDs)	
Thermisters - PTC , 1 number per phase			Brake (Type/voltage/torque)	
Additional T-Box for Accessories				
Additional nameplate				

Notes:

1)All performance values are subject to IS/IEC 60034-1 tolerances, unless otherwise specified.

2)Performance values are at rated voltage and rated frequency condition and for DOL starting condition.

3)Motor GD^2 = Load GD^2 assumed wherever not mentioned.

4)Where starting time is more than 10 seconds, provision of heavy duty relays is mandatory.

5)Kilowatt rating is mandatory and HP is approximate.

6) Accessories provided are marked as "YES"

Prepared by	
Approved by	
Revison	

Project:		Contractor/Client		Date:
Consultant		Package		